

**ROAD CLOSURE BARRY WAY
Wallaces Lookout
(South bound)
6/11/2021
Perth to Sydney Marathon Rerun 2021**

Distance From Wallace Craigie Lookout to Snowy River Way = 35.8km

BARRY WAY CLOSED
WALLACE CRAIGIE
LOOKOUT

ROAD CLOSED
AHEAD

Locate 100 m south of Muzzelwood Place

Glennrada

VMS Board to be located 100 m south of Snowy River Way advising of road closure ahead



Wallace Craigie Lookout

TO VICTORIA



Manifest	
2 x	R4-1 (40) SPEED LIMIT 40
1 x	G9-79 (40) SPEED LIMIT 40 AHEAD
1 x	Sign
1 x	Stop-Slow Bat
1 x	T1-18 PREPARE TO STOP
1 x	T1-34 TRAFFIC CONTROLLER AHEAD
1 x	T1-5 WORKERS AHEAD
1 x	T2-4 ROAD CLOSED
1 x	T2-4-Q02a ROAD CLOSED AHEAD
1 x	Traffic Controller

NSW SafeWork NSW WORK HEALTH & SAFETY TRAFFIC CONTROL WORK

Jamie Bruce
CAMIN
Card No: TCT1014760
Date of Issue: 01/08/2021
Type of traffic control work: PWZ IMP TCR
D.O.B: 11/01/1973



Date: 08/07/2022 Author : Jamie Camin Project: SHORT TERM ROAD CLOSURE
Plan No.: RTSJ148 CLIENT: PERTH-SYDNEY MARATHON SCALE: N.T.S

- Comments:
1. ALL TEMPORARY TRAFFIC MANAGEMENT DEVICES ARE TO BE IN ACCORDANCE WITH A.S. 1742.3 2009
 2. ALL SIGN FACINGS SHALL BE OF CLASS ONE MATERIALS AS SPECIFIED AS/NZS 1906.1
 3. ALL SIGNS AND DEVICES SHALL BE ERECTED WITHIN LINE OF SIGHT OF THE ROAD USERS. THEY SHALL NOT BE OBTURED BY VEGETATION OR PARKED VEHICLES & SHALL BE POSITIONED WHERE THEY DO NOT BECOME A HAZARD TO PEDESTRIANS OR VEHICLES
 4. ALL CONFLICTING SIGNAGE INCLUDING PARKING SIGNS WITHIN THE WORK SITE SHALL BE COVERED OR REMOVED WHILE WORK IS IN PROGRESS
 5. CLEARANCE TO TRAFFIC TO BE MAINTAINED GREATER THAN 1.2 METERS
 6. TRAFFIC CONTROLLERS TO MAINTAIN RADIO CONTACT AT ALL TIMES
 7. EDGE CLEARANCE (signs) FROM TRAVEL WAY <60 KM/H = 0.5M.
 8. PLAN MAY BE SUBJECT TO CHANGE +25% -10%
 9. RISK ASSESSMENT TO BE MADE AND RECORDED PRIOR TO IMPLEMENTATION AND RECORDED ON RTS SITE SAFETY & ENVIRONMENTAL HAZARD ASSESSMENT FORM